Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

THE BALDWIN LOCOMOTIVE WORKS

SPECIFICATION

NO. C-7626

CLASS 12 28 1/4 E

CODE WORD --

FOR TEMPLE LUMBER COMPANY

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

1856—2M—6-20

INQ. **As Built**

FILE **WJD:JJF**

THE BALDWIN LOCOMOTIVE WORKS

PHILADELPHIA **July 1, 1922.**

Class **12 28 1/4 E** SPECIFICATION No. **C-7626** Drawing No. **8**

Of a **MIKADO TYPE** Locomotive Engine having **four** pairs of coupled wheels **with a two-wheeled truck at front and back.**

For **TEMPLE LUMBER COMPANY**

This specification may be designated in cabling by code word **—**

GENERAL DIMENSIONS


Gauge	4	Ft.	8-1/2	Ins.	Fuel	Oil	
Cylinders	Simple		Dia.	17	Ins. Stroke	24	Ins.
Drivers, Diameter	44	Ins.	Working Pressure			175	Lbs.
Wheel Base, Driving				12	Ft.	3	Ins.
" " Total Engine				27	Ft.	6	Ins.
" " Engine & Tender				53	Ft.	2-1/2	Ins.
Weight In Working Order (~~Approximate~~)	on Drivers			99,150			Lbs.
	on F. Truck			14,500			Lbs.
	on B. Truck			13,000			Lbs.
	Total Engine			126,650			Lbs
	Tender			91,200			Lbs.
Water Capacity	4,500	Gallons					
Fuel Capacity	1,200	"					

Boiler, Diameter	56	Ins. Type	Ext. Wagon Top	
Fire Box	78	Ins. Long	40-7/8	Ins. Wide
Tubes No.	190	Dia. 2 Ins.	Length 14 Ft. 0	Ins.
" "	—	" — "		
Heating Surface (~~approximate~~) Fire Box			105	Sq Ft.
Fire Brick Tubes			—	"
Tubes			1385	"
"			—	"
Total			1490	Sq. Ft.
Grate Area	22.2	Sq. Ft.	Ratio to Heat. Surf. 1 to	67
Superheating Surface	—		Sq. Ft.	
Tractive Power (at .85 working pressure)			23,450	Lbs.
Ratio of Adhesion	4.2			

Limiting Conditions **All parts where possible interchangeable with 12 30 1/4 E 36. Locomotive for operation in Texas. Curves 30 degrees.**

NOTE:— Locomotive Baldwin Class 12 28 1/4 E 21, Road No. 18, as built in 1922.

Type generally illustrated by **Photograph 4438.**



Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

DETAILS OF CONSTRUCTION

BOILER

Made of plates of homogeneous steel for a pressure of **200** lbs. per square inch, and tested with steam to at least 20 lbs. per square inch, above the boiler pressure, and with hot water to one-third above the boiler pressure. **Safety valves set to 175 lbs. working pressure.**
Waist **56** inches in diameter at smoke box end, made **extended wagon** top, with one dome placed **forward of firebox** Waist plates **9/16 & 5/8** inch thick.
All longitudinal seams **butt jointed, double covering strips.**

Dome

Of open-hearth steel, pressed out in one piece, ~~or built up with separate top, base and body section.~~
Dome cap of forged steel.
Auxiliary dome **None**

Tubes

Of **Steel** No. **12** **B.** wire gauge,
Of **-** No. **-** wire gauge,
with copper ferrules and swaged at ends in firebox tube sheet.
190 *in number* **2** inches in diameter,
- in number **-** inches in diameter, } and **14** feet **0** inches in length.

Fire Box

78 inches long and **40-7/8** inches wide inside, of homogeneous steel, side sheets **3/8** inch thick, back sheet **5/16** inch thick, crown sheet **3/8** inch thick, flue sheet **1/2** inch thick. Water space **3** inches sides and back, **4** inches front. Water space frame **double** riveted. **Crown and side sheets in one piece.**

Fire Brick Arch

NONE Firebox lined with firebrick for oil burning.
Flexible staybolts of threaded type; other staybolts hollow.

Stay Bolts

Water space stay bolts of iron, screwed and riveted to inside and outside sheets.

Crown Staying

Radial stay bolts of iron, screwed through crown sheet and roof of firebox.

FLEXIBLE STAYS

Tate Flexible Stays, about 300 in number, located in breaking zone.

Boiler Covering

Boiler lagged with approved magnesia **sectional** boiler covering, neatly jacketed with **No. 22 B. W. G. Polished Steel** and secured by ~~iron~~ **steel** bands.
Dome lagged with same material as boiler, with painted ~~iron~~ **steel** casing on body. Casing to have ~~cast iron~~ **steel** bottom ring and ~~cast iron or~~ **pressed** steel top ring.

Boiler Fittings

Whistle **Nathan Chime 963-A-1070** Blow-off cock **One**
Safety valves **Two CROSBY 2-1/2" Open, Style HA-110**
Blower valve, **7" ASHCROFT** steam gauge, and **One B. L. W.** glass water gauge, with lamps, gauge cocks. **Whistle as Fig.1782 of Loco. Dictionary, 1919 Edition.**

Feed Water

Supplied by **Two Ohio Class "A" No. 8 Injectors.**
Baldwin injector check with stop valves.

Superheater

N O N E

OIL BURNING ARRANGEMENT

Oil Burning Arrangement Baldwin Standard, with burner placed in front end of firebox.
Royalty payable by The Baldwin Locomotive Works.

Cleaning Holes

Located where necessary for proper cleaning of boiler. Fusible plug located in crown sheet, ~~and one spare fusible plug furnished extra.~~ **Washout plugs same location as on 12 30½ E 36**

Steam Pipes

Of iron, in smoke box. Dry pipe of steel, inside of boiler.

Throttle Valve

Balance poppet throttle valve of cast iron, in vertical arm of dry pipe.

~~Grates~~ Fire Pan

Firebrick pavement in pan.
With dampers suitably located

Smoke Stack

Cast iron tapered stack 12-3/4" diam. at smallest point and to have extension into smokebox to act as cleaning pipe.

Smoke Box

Smokebox extension short with adjustable deflecting plates.
Smokebox front and door of pressed steel.

C-7626

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

CYLINDERS Of close-grained iron, as hard as can be worked.
High pressure cylinders **17** inches diameter and **24** inches stroke.
Low pressure cylinders **-** inches diameter and **-** inches stroke.

Cylinder Heads Of cast **iron** , neatly covered.

Main Valves Type **Richardson Balanced, with Vacuum Valves** operating in suitable steam chests.

Cylinder Covering Cylinders lagged with same material as boiler and neatly cased with painted ~~iron~~ **steel**

Lubricator **Chicago Triple Bull's Eye** automatic sight feed lubricator, placed in cab, and connected to steam chests by suitable pipes. **of iron under jacket.**

Pistons Heads of **cast iron** fitted with ~~approved form of steam packing~~ **cast iron rings sprung in.** Piston rods of steel, ground and keyed ~~or bolted~~ to crossheads, and securely fastened to piston heads.

Packing Metallic packing for piston rods and valve stems **United States, King Type**

Guides Of steel, fitted to guide yoke of mild wrought steel, or cast steel. **Needle oil cups on guides**

Crosshead Of cast **steel** , with suitable bearings. **of cast iron, tinned.**
"Alligator" type crosshead.

Valve Motion **Walschaert's** graduated to cut off equally at all points of stroke.
Valve gear similar to 12 30 1/4 E 36.

DRIVING WHEELS **E I G H T** in number, **44** inches in diameter. Centers of cast **steel**

turned to **37** inches diameter. **Tires held by shrinkage and shoulder.**

Tires Of ~~steel~~ **Hard** , **3-1/2** inches thick when finished; **Front and Back**
pairs flanged **5-1/2** inches wide, **Intermediate** pair plain **6-1/2** inches wide.

Driving Axles Of hammered steel, journals { main **7-1/2** inches diameter and **8** inches long.
others **7-1/2** inches diameter and **8** inches long.

Driving wheels to have bronze hub liners. Rail washers to be applied, same as on 12 30 1/4 E 36.

Driving Boxes Of **Cast Steel** , with bronze bearings.

Rods Equalizing beams of wrought steel or cast steel.
Connecting and Parallel rods of hammered steel. Connecting rods forged solid, and furnished with all necessary straps, keys and brasses. Parallel rods with ~~straps, keys and brasses or with~~ solid ends and heavy bronze bushings, put in by hydraulic pressure and well secured from turning in rod.
Side rods same as on 12 30 1/4 E 36, with grease cups forged on.

Wrist Pins Of Steel. **All tires on same axles to be exactly the same circumference.**
All tires from Standard Steel Works.

FRONT ENGINE TRUCK **T W O** wheeled truck
Truck frame of ~~wrought steel or~~ cast steel, well braced, fitted with swing bolster, with center bearing, ~~side bearing, or radiating mechanism~~

Wheels **Cast iron, spoke center, steel tired** wheels **28** inches diameter.

Axles Of hammered steel, with journals **4-1/2** inches in diameter and **7-1/2** inches long.
Boxes of cast **iron** , with bronze bearings.
Tires 2-1/2" x 5-1/2" held by shrinkage and shoulder.

BACK ENGINE TRUCK **T W O** wheeled truck
Truck frame of ~~wrought steel or~~ cast steel, well braced, fitted with swing bolster, with side bearing, ~~with center bearing, or radiating mechanism~~

Wheels **Cast iron, spoke center, steel tired** wheels **28** inches diameter.

Axles Of hammered steel, with journals **4-1/2** inches in diameter and **7-1/2** inches long.
Boxes of cast **iron** , with bronze bearings.
Tires 2-1/2" x 5-1/2" held by shrinkage and shoulder.

C-7626

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

Engine Springs	Of steel, tempered in oil. **from Standard Steel Works**
FRAMES	Of **Cast Steel** , securely braced and provided with front and back lugs for cylinder connections, and with pedestal caps fitted and bolted to bottom of pedestal. **Frames and springs to be made for rough track conditions.**
Gibs and Wedges	Of cast iron.
PILOT	**Of wood, braced with iron.**
Bumpers	Front, of **wood** Back, of **bar steel**
CAB	Substantially built of **steel** well finished and substantially put together. **Ventilator in cab roof.**
	Hand rails of iron. **to run full length of boiler, same as shown on Photo.4438.**
	Running boards **of steel** Cab boards of **steel, covered with wood**
Fixtures	Engine furnished with **two** sand box**es** , bell and cord. **Gollmar Air Bell Ringer.** **One pair of wrecking frogs.**
Headlight	**Two 16" round case headlights, fitted with Pyle National Type K-2 incandescent electric equipment, one front and one back of engine.** **Rear headlight on top of cab.**
Power Brake	**Westinghouse-American outside equalized combined automatic and straight air brakes, Schedule 6-ET, WN-1, BC and 1212, on all driving and tender wheels with train connections front and rear. One 9-1/2" air pump, left side.** **Air pump exhaust piped into cylinder saddle.**
Couplers	**Sharon M. C. B. automatic couplers, with slotted knuckle, 33-1/2" center above top of rail, at front of engine and rear of tender.**
Sander	**Leach trap A-1 air sander in each box, to sand front and back.** **Sander same as for 12 30 1/4 E 36.**
Steam Heat	**None.**
PAINTING, LETTERING, ETC.	**Painting style, Olive Green and Aluminum.** **Lettering in Silver.** **Mark on tank sides:- TEMPLE LUMBER COMPANY** **Road No. 18 on Front Number Plate, Front Sand Box, Cab Sides and Back of Tank.**
REVERSE	**Reverse lever quadrant to be notched same as on 12 30 1/4 E 36.**

C-7626

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

TENDER

Frame Substantially built of **8" and 10" steel channels** strongly braced
Front and back bumpers of cast steel.

Tank Of steel, strongly put together, with angle iron corners and well braced.
Water capacity **4,500** gallons of (231 cubic inches). Fuel capacity **1,200 Gallons.**
Shape of tank **"U" shape, straight top.**

Trucks Two four-wheeled center bearing trucks, ~~made with steel or iron side bars.~~ **Equalized type trucks, center bearing spparate from truck bolster.**

Bolsters Bolsters of **cast steel**

Additional bearings at sides of back truck

Springs Of steel, tempered in oil. **Elliptic, from Standard Steel Works.**

Wheels **Chilled Cast Iron Plate** wheels **30** inches diameter.
Brakes on all wheels.

Axles Of hammered steel, outside journals **4-1/4** inches diameter and **8** inches long.
Oil tight boxes, with bronze bearings.

Tool Boxes Of **wood** fitted with locks and keys **and located on top of tank.**

Tender of long low design.

Oil gauge graduated in inches to be placed on front end of oil tank.

Drain pipe through coping of tender, to drain overflow.

Chafing casting and drawbar casting on engine and tender, of cast steel.

Oil burning arrangement with open and close heater in tank.

C-7626

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

THE BALDWIN LOCOMOTIVE WORKS

Material Specifications

Issued September 1, 1919

GENERAL

All material applied on this contract shall be of the best quality of its respective kind, and conform to the requirements of the American Society for Testing Materials (A. S. T. M.) as condensed in The Baldwin Locomotive Works specifications, and the following synopsis:

Boiler and Firebox Steel No. 130

The steel shall be made by the open-hearth process and shall be furnished in two grades, viz: Flange and Firebox. Each plate shall conform to the following chemical and physical requirements:

	Flange	Firebox
Carbon		0.12—0.25%
Manganese	0.30—0.60%	0.30—0.60%
Phosphorus (Acid Process) Not over	0.05%	0.04%
" (Basic ") " "	0.04%	0.035%
Sulphur	0.05%	0.04%
Tensile Strength—lbs. per sq. in.	55,000-65,000	52,000-62,000
Yield Point—Minimum lbs. per sq. in.	0.5 Tens. Str.	0.5 Tens. Str.
Elongation in 8"—Minimum per cent.	$\frac{1,500,000}{\text{Tensile Str.}}$	$\frac{1,500,000}{\text{Tensile Str.}}$

Firebox Copper No. 211

The copper shall be fire refined and hot rolled from cakes. One tension test and one bend test shall be made from each plate as rolled and shall conform to the following requirements. Arsenical copper shall contain 0.25 to 0.50 per cent. of Arsenic and shall not contain more than 0.120 per cent. of impurities.

Tensile Strength—lbs. per sq. in ..... Not under 31,000
Elongation in 8"—Minimum per cent 35

Tension test specimens shall be taken from full thickness plate as rolled and the thickness of each plate shall not be more than 0.04" under size ordered, and shall be free from injurious defects. A specimen shall bend both hot *(500-700 C) and cold, 180°, without cracking on the outside of the bent portion for material not over 1" in thickness.*

Staybolts-Iron No. 139

Iron shall be made wholly from re-worked puddled pig iron or re-worked knobbled charcoal iron, and shall be free from any admixture of iron scrap or steel. Iron shall conform to following physical requirements:

Tensile Strength—lbs. per sq. in ..... 48,000-52,000 Elongation in 8"—Minimum per cent 30
Yield Point—Minimum ..... 0.6 Tens. Str. Reduction of Area 48%

A test specimen shall bend cold through 180° flat on itself in both directions, without fracture on the outside of the bent portion. Bars shall be round, smooth, free from injurious defects and shall take a smooth, clean thread.

Staybolts-Copper No. 212

The copper shall conform to the same chemical and physical requirements as are given for copper plates for fireboxes. The bars shall be round and shall be free from injurious defects.

Lap-Welded and Seamless Steel Boiler Tubes No. 128

Steel shall be made by the open-hearth process and shall conform to the following requirements:

Carbon ..... 0.08—0.18% Phosphorus ..... Not over 0.04%
Manganese ..... 0.30—0.60% Sulphur ..... " " 0.045%

One flange, one flattening, one crush test shall be made from each of two tubes in each lot of 250 or less. Each tube shall be subjected to an hydrostatic test of 1000 lbs. per sq. in. for tubes under 5 inches diameter, and 800 lbs. per sq. in. for tubes 5 inches diameter and over.

Lap-Welded Charcoal Iron Boiler Tubes No. 138

Tubes shall be made from knobbled, hammered charcoal iron and shall be free from injurious defects and distortions.
One tube in each lot of 250 or less shall be tested and shall conform to the following physical requirements:
Each tube shall be subjected to an hydrostatic test of 1000 lbs. per sq. in. for tubes under 5 inches diameter, and 800 lbs. per sq. in. for tubes 5 inches diameter and over.
Hot bend, nick bend and crushing tests shall be made.

Seamless Brass Boiler Tubes No. 214

Tubes shall be drawn to size and semi-annealed. They shall be fully annealed at both ends if so ordered and shall conform to the following requirements:

Copper ..... Not under 69.00% Material other than copper and zinc ... Not over 0.50%
Lead ..... Not over 0.50% Zinc ..... Remainder
Iron ..... " " 0.10%

Test specimens taken from semi-annealed tubes shall be fully annealed for testing.
All tubes shall stand an internal hydrostatic pressure of at least 750 lbs. per sq. in. One flange and one flattening test shall be made from each of 2 tubes in each lot of 250 or less. Tubes shall be circular within 0.02" and shall be free from injurious defects.

Seamless Copper *Boiler Tubes No. 213*

Tubes will be furnished hard or annealed as specified.
All tubes shall stand an internal hydrostatic pressure of 750 lbs. per sq. in. This test should be made before the tubes are annealed.
One flange and one crush test shall be made from each of two tubes in each lot of 250 or less.
All specimens shall be tested cold.
All tubes shall be circular within 0.02" and shall be free from injurious defects.

Boiler Rivet Steel No. 131

Steel shall be made by the open-hearth process and shall conform to the following chemical and physical requirements:

Manganese ..... 0.30—0.50% Tensile Strength—lbs. per sq. in. 45,000-55,000
Phosphorus ..... Not over 0.04% Yield Point—Minimum lbs. per sq. in. 0.5 Tens. Str.
Sulphur ..... " " 0.045% Elongation in 8"—Minimum per cent. $\frac{1,500,000}{\text{Tensile Str.}}$ But not to exceed 30%

Carbon Steel Forgings Annealed No. 120

Forgings for carbon-steel driving axles, engine and trailing truck axles, main and side rods, straps, crank pins and piston rods shall be made of open-hearth steel and conform to the following chemical and physical requirements:

Manganese ..... 0.40—0.70% Phosphorus ..... Not over 0.05%
Sulphur ..... Not over 0.05%

SIZE OUTSIDE Diam. or Overall Thickness	Tensile Strength lbs. per sq. in.	Yield Point lbs. per sq. in.	Elongation in per cent. Not Under	Reduction of Areas per cent Not Under
Not over 8"	80,000	0.5 Tens. Str.	20	32
Over 8-12" inclusive	80,000	0.5 " "	19	30
" 12-20" "	80,000	0.5 " "	18	28

All such forgings to be annealed.
One tension test shall be made from each melt in each annealing charge.
Chemical analysis shall be made from each melt. One tension and one bend test may be made from each melt in each quenching charge. Tension and bend test pieces may be cut out from prolongations on a forging.

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

Welding Steel Forgings No. 118

Mild steel forgings which may be welded or case hardened shall conform to the following requirements:

Manganese	0.30—0.55%	Elongation in 2"—Minimum per cent.	$\frac{1,500,000}{\text{Tens. Str}}$
Phosphorus	Not over 0.05%		
Sulphur	" " 0.05%		
Tensile Strength—lbs. per sq. in	47,000-60,000	Reduction of Area—Minimum per cent.	$\frac{2,500,000}{\text{Tens. Str.}}$
Yield Point—lbs. per sq. in	0.5 Tens. Str.		

Wrought Iron Bars No. 141

Refined wrought iron bars shall be made wholly from puddled iron, free from any admixture of steel, and shall conform to the following minimum physical requirements:

Tensile Strength—lbs. per sq. in	48,000	Elongation in 8"	22%
Yield Point—lbs. per sq. in	25,000		

For material over 4 sq. in. in section area a reduction shall be allowed of 250 lbs. for each additional sq. in. in area.
No bar shall be used which shows a tensile strength less than 45,000 lbs. per sq. in.
Cold bend, hot bend and nick tests shall be made in accordance with A. S. T. M. Standards.

Tender and Engine Truck Axles No. 121

Steel shall be made by the open-hearth process and shall conform to the following requirements:

Carbon	0.35—0.55%	Phosphorus	Not over 0.05%
Manganese	Not over 0.70%	Sulphur	" " 0.06%

An analysis shall be made from each melt, and one drop test shall be made from each melt.

Bearing Metals No. 217

Principal bearings will be made from metal of composition Class No. 1 or Class No. 2. (As itemized in complete specification No. 217)

	No. 1	No. 2		No. 1	No. 2
Tin	9 to 11%	4 to 6%	Antimony—Maximum	0.25%	0.50%
Lead	9 to 11%	22.5 to 26.5%	*Phosphorus—Maximum	1.0%	.....
Zinc—Maximum	0.75%	0.75%	Total impurities, including Zinc—Maximum	1.0%	1.5%
Iron—Maximum	0.25%	0.40%	Copper—Per Cent	Remainder	Remainder

*Can be specified at option of purchaser.

Steel Castings No. 127

Steel castings for the principal parts of locomotives, such as engine frames, wheel centers, etc., shall conform to the following chemical and physical requirements:

Phosphorus	Not over 0.05%	Sulphur	Not over 0.05%
Tensile Strength—lbs. per sq. in	70,000	Elongation in 2"	18%
Yield Point—lbs. per sq. in	0.45 Tens. Str.	Reduction of Area	25%

Coupons shall be attached to all important castings.

Cylinders No. 145

Cylinder castings to be of tough gray iron, close grained and cast in a dry mould. Standard arbitration bars, cast independently, shall show an average transverse strength of not less than 3200 lbs. and an average deflection of not less than 0.09 in. when placed horizontally on supports 12 inches apart. Drillings from transverse test bars shall show the following:

Phosphorus	Not over 0.90%	Sulphur	Not over 0.12%

Gray Iron Castings No. 148

Castings to be of tough gray iron, free from defects, and must show a sulphur content not exceeding 0.10% for medium castings and 0.12% for heavy castings.
Transverse tests on a standard arbitration bar shall show a minimum transverse strength of 2900 lbs. for medium castings and of 3300 lbs. for heavy castings.
In no case shall the deflection of a standard arbitration bar be under 0.10 in. when placed horizontally on supports 12 inches apart.
One transverse test to be made from each melt.

Springs No. 161, No. 162

All springs shall conform to the following chemical requirements:

Carbon	0.90—1.10%	Phosphorus—Maximum	0.05%
Manganese—Maximum	0.50%	Sulphur "	0.05%

Springs shall be true to drawings, subject only to slight variations from the free and loaded heights, etc., specified in The Baldwin Locomotive Works' specifications.

Steel Tires No. 126

Steel tires shall be furnished in three classes.
Class A for driving tires for passenger locomotives.
Class B for driving tires for freight locomotives and tires for locomotive truck, tender truck, trailer and car wheels and miscellaneous service.
Class C for driving tires for switching locomotives.
The steel shall conform to the following requirements:

Carbon Class A	0.50—0.70%	Manganese	Not over 0.75%
Carbon Class B	0.60—0.80%	Phosphorus	" " 0.05%
Carbon Class C	0.70—0.85%	Sulphur	" " 0.05%
		Silicon	0.15—0.35%

	Class A	Class B	Class C
Tensile Strength—lbs. per sq. in	105,000	115,000	125,000
Elongation in 2"	12%	10%	8%
Reduction of area	16%	14%	12%

One analysis and one tension test shall be made from each melt. The test specimen is to receive approximately the same amount of work as the tire which it represents.

Chilled Wheels

Of approved make and of following guaranteed mileage:

For 28" wheels	40,000 miles	For 33" wheels	50,000 miles
For 30" wheels	45,000 miles	Other sizes in proportion.	

Adopted by joint committee Master Car Builders' Association, American Rwy. Master Mechanics' Association, and Association of Manufacturers of Chilled Car Wheels, November 21, 1889.
Deficient mileage will be adjusted upon the return of defective wheel, or that part of same containing the defect causing withdrawal from service. If preferred, wheels will be furnished subject to approved specifications and drop test without mileage guarantee.

Wrought Steel Wheels No. 157

Steel shall be made by the open-hearth process and shall conform to the following requirements:

	Acid	Basic		Acid	Basic
Carbon	0.60—0.80%	0.65—0.85%	Sulphur	Not over 0.05%	0.05%
Manganese	0.55—0.80%	0.55—0.80%	Silicon	0.15—0.35%	0.15—0.30%
Phosphorus	Not over 0.05%	0.05%			

An analysis shall be made from one wheel of each melt.


Structural Steel No. 110

Steel shall be made by the open-hearth process and conform to the following chemical and physical requirements:

Phosphorus	Not over 0.05%	Sulphur	Not over 0.05%
Tensile Strength—lbs. per sq. in			55,000-65,000
Yield Point—Minimum lbs. per sq. in			0.5 Tens. Str.
Elongation in 8"—Minimum per cent			$\frac{1,500,000}{\text{Tensile Str.}}$

One tension and one bend test to be made from each melt.

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076



The style and position of the couplers and buffers desired are vital points to be considered in the design of a locomotive.

To facilitate cabling in cases where the order is placed in that way, we have indicated the necessary cable code designations.

DAS	Two pocket coupling heights respectively	CUX	Height from top of rail to center of coupling is
CUV	Full particulars regarding couplings by first mail	CUM	Distance apart center to center of buffers
DAV	Distance apart center to center of hooks	DAP	Three pocket coupling heights respectively

IMPORTANT—SPECIFY STYLE AND HEIGHT OF COUPLER WITH ORDER

Please detach this sheet and return it with the order, indicating style of couplers desired and the correct dimensions.

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

THE BALDWIN LOCOMOTIVE WORKS

Standard Practices to be Followed Unless Otherwise Specified

Boiler Construction

All boiler and fire box seams caulked inside and outside where possible. All holes reamed perfectly true after sheets are put together, holes slightly countersunk on inside and outside edges.

All caulking edges of plates planed where possible and caulked with round-pointed caulking tool, insuring plates against injury by chipping, in caulking with sharp-edged tools. All boiler brace jaws drop forged, with holes drilled. All rivet and pin holes in braces to be drilled. All jaw-pins to be turned to give full body bearing on both sides of jaw. All T-irons fastened to the interior of boiler shell to be accurately fitted to boiler. Tube-sheets to be thoroughly annealed and tube holes accurately reamed to gauges; sharp corners carefully rounded, to avoid cutting tubes in setting.

Throat sheet of sufficient thickness to prevent undue thinning where flanged. All parts well and thoroughly stayed. Liners on inside of side sheets, providing double thickness of metal for studs of expansion braces, when necessary.

Fire Box Construction

Fire door opening formed by flanging and riveting together the inner and outer sheets, except on small engines. Tool guard to be cast on lower part of fire door frame.

Provision to be made for vertical expansion of fire box tube sheet, if diameter of waist is 46 inches or over.

Outside and inside surfaces of water space frame, against which the sheets of the fire box and outer shell are riveted, to be machined smooth and fitted to gauges.

All water space stay bolts to have three-sixteenths-inch hole, one and one-quarter inches deep from outside, to indicate when broken in service. All stay bolt threads turned off between sheets.

Dome Construction

"One-piece": Pressed from single sheet of open-hearth steel, of sufficient thickness to prevent undue thinning where flanged; or if

"Built-up": To have top ring and bottom flange of seamless open-hearth forged steel, turned and accurately fitted to open-hearth steel body sheet before being drilled and riveted.

Dome base flange to be radially planed to fit the outer shell of boiler. All rivets connecting dome to boiler to be driven by hydraulic pressure.

Cylinders and Machinery

Cylinders accurately planed and fitted, and bolted together in the most approved manner. Valve face and steam chest seat raised above face of cylinder to allow for wear, except when piston valves are used. As far as possible, when placed horizontally, right and left hand cylinders to be reversible and interchangeable.

Valve motion: links, sliding-blocks, pins, lifting links and eccentric rod jaws to be well case hardened, or provided with hardened bushings. Sliding-blocks designed so as to give ample wearing surface. Rock-shafts and reverse-shaft of wrought iron or cast steel.

Lubrication of all bearings carefully provided for, and oil cups attached where required.

Finish and Equipment

Cylinder head covers of hydraulic forged steel. Steam chest bodies cased with painted iron, except when piston valves are used.

Cab to be provided with suitable windows and doors, conveniently arranged, and glazed with first quality double American crystal glass. Cab seats, cab seat cushions and an engineer's arm rest to be provided.

If for use in United States, ash pans, couplers, steps and hand-holds to be in accordance with the requirements of the Interstate Commerce Commission.

TOOLS: Two jack-screws and levers, one pinch-bar, with steel point and heel, suitable wrenches to fit all nuts and bolts on engine, including two monkey-wrenches, one set of driving-box packing tools, one machinist's hammer, one soft hammer, three cold chisels (two flat and one cape), and one engineer's torch.

CANS: One long spout quart oil can, one two-gallon oil can, one tallow pot.

FIRING IRONS: To suit fuel.

Painting

Engine and tender to be well painted and varnished. Lettering and numbering to be painted as specified by purchaser.

Case Hardening

All finished movable nuts made of steel, or iron case hardened.

Threads

All threads on bolts to be United States standard.

Gauges

All principal parts of engine accurately fitted to gauges and templets, and thoroughly interchangeable.

Patents

Builders not responsible for patented appliances specified by purchaser.

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

Boiler Form No. 4

B. L. W. Form 491
6M 2-21

12 28 1/4 E 21

THE BALDWIN LOCOMOTIVE WORKS

-B-

Specification Card for Locomotive No. 18

Owned by ..... TEMPLE LUMBER ..... Railroad Company.

Operated by ..... TEMPLE LUMBER ..... Railroad Company.

Builder, The Baldwin Locomotive Works.
Builder's No. of Boiler 55382
When built ..... MAY, 1922.
Where built ..... EDDYSTONE, PENNA.
Type of boiler EXT. WAGON TOP-RADIAL STAYS
Material of boiler shell sheets .. STEEL
Material of rivets ..... STEEL
Dome, where located .... ON 3RD COURSE
Grate area in sq. ft. 22.2
Height of lowest reading of gauge glass above crown sheet ..... 3 1/4"
Height of lowest gauge cock above crown sheet .... 3 1/4"
Water-bar tubes, O. diam. .... --- .... thickness. ---
Arch tubes, O. diam. ..... --- .... thickness. ---
Fire tubes, number 190
" " O. diam. ..... 2" ..... length ... 168"

Safety valves:

No.	Size	Make	Style
2	2 1/2"	CROSBY	OPEN

Firebox stay bolts, O. diam. .. 7/8" .. spaced 3.86" x 4"
Combustion chamber stay bolts, O. diam. .... ---
" " " " " spaced ... --- ... x ... ---
Crown stays, O. diam., top .... 1" ..... bottom ... 1"
" " spaced .. 3.99" ..... x 3.835"
Crown-bar rivets, O. diam., top .... --- .... bottom --- ....
" " " spaced ..... --- ..... x ..... ---
Water space at firebox ring, sides ..... 3"
back ..... 3" ..... front ..... 4"
Width of water space at sides of firebox measured at center line of boiler, front .... 5" .... back ... 8"

Shell sheets:

Front tube	1/2"	thick.	
1st course	9/16"	"	54 7/8" I. diam.
2d "	5/8"	"	56" TO 60" "
3d "	5/8"	"	61 1/4" "
4th "	---	"	--- "

Mem.: When courses are not cylindrical give inside diameter at each end.

Firebox:
Thickness of sheets—
Tube .... 1/2" .... Crown ... AND .. Sides .. 3/8" ....
Door .. 5/16" .... Combustion chamber. --- ....
Inside throat (if tube sheet is in two pieces) .... ---


External firebox:
Thickness of sheets—throat 11/16" .. back head .. 1/2" ..
Roof ..... AND ..... sides .. 9/16" .....
Dome inside diam. .... 29" .....
Thickness of sheet .. 3/4" .... base .. 1" .... liner .. 5/8" ....

Were you furnished with authentic records of the tests of materials used in boiler? ..... YES .....

Records on file in the office of the Test Department of The Baldwin Locomotive Works show that the lowest tensile strength of the sheets in shell of this boiler is:

1st course	57600	pounds per sq. in.
2d "	57500	" " " "
3d "	59000	" " " "
4th "	---	" " " "

Is boiler shell circular at all points? ... YES .....
If shell is flattened, state location and amount .....
..... ---- .....
Are all parts thoroughly stayed? ..... YES .....
Are dome and other openings sufficiently reinforced?
..... YES .....
Is boiler equipped with fusible plugs? ..... YES .....



SEAM ON 1st COURSE

SEAM ON 2nd COURSE

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

Boiler Form No. 4

B. L. W. Form 491
6M 2-21

12 28 1/4 E 21

THE BALDWIN LOCOMOTIVE WORKS

-B-

Specification Card for Locomotive No. 18

Owned by ..... TEMPLE LUMBER ..... Railroad Company.

Operated by ..... TEMPLE LUMBER ..... Railroad Company.

Builder, The Baldwin Locomotive Works.
Builder's No. of Boiler.... 55382
When built..... MAY., 1922.
Where built ..... EDDYSTONE, PENNA.
Type of boiler. EXT. WAGON TOP-RADIAL STAYS
Material of boiler shell sheets.. STEEL
Material of rivets..... STEEL
Dome, where located.... ON 3RD COURSE
Grate area in sq. ft..... 22.2
Height of lowest reading of gauge glass above crown sheet ..... 3 1/4"
Height of lowest gauge cock above crown sheet.... 3 1/4"
Water-bar tubes, O. diam.... ---- ...thickness. ----
Arch tubes, O. diam..... ---- ...thickness. ----
Fire tubes, number..... 190
" " O. diam..... 2" .....length ...168"

Safety valves:

No.	Size	Make	Style
2	2 1/2"	CROSBY	OPEN

Firebox stay bolts, O. diam... 7/8" ..spaced 3.86" x 4"
Combustion chamber stay bolts, O. diam.... ----
" " " " " spaced... ---- x. ----
Crown stays, O. diam., top.... 1" ..... bottom... 1"
" " spaced .. 3.99" ..... x 3.835"
Crown-bar rivets, O. diam., top..... bottom. ----
" " " spaced ..... ---- x. ----
Water space at firebox ring, sides..... 3"
back ..... 3" ..... front ..... 4"
Width of water space at sides of firebox measured at center line of boiler, front .... 5" .... back .. 8"

Shell sheets:
Front tube..... 1/2" .....thick.
1st course .... 9/16" ..... " .54 7/8" .....I. diam.
2d " ... 5/8" ..... " 56" TO 60" .. "
3d " ... 5/8" ..... " 61 1/4" ..... "
4th " .... ---- ..... " .... ---- ..... "


Mem.: When courses are not cylindrical give inside diameter at each end.

Firebox:
Thickness of sheets—
Tube..... 1/2" ....Crown ... AND .. Sides .. 3/8" ....
Door .. 5/16" ....Combustion chamber. ----
Inside throat (if tube sheet is in two pieces) .----...

External firebox:
Thickness of sheets—throat 11/16" .. back head .. 1/2" ...
Roof..... AND ..... sides .. 9/16" .....
Dome inside diam. .... 29" .....
Thickness of sheet. 3/4" ....base.. 1" ....liner.. 5/8" ....
Were you furnished with authentic records of the tests of materials used in boiler?..... YES .....
Records on file in the office of the Test Department of The Baldwin Locomotive Works show that the lowest tensile strength of the sheets in shell of this boiler is:
1st course ..... 57600 ..... pounds per sq. in.
2d " ..... 57500 ..... " " " "
3d " ..... 59000 ..... " " " "
4th " ..... ---- ..... " " " "
Is boiler shell circular at all points?.... YES .....
If shell is flattened, state location and amount.....
..... ----.....
Are all parts thoroughly stayed?..... YES .....
Are dome and other openings sufficiently reinforced?
..... YES .....
Is boiler equipped with fusible plugs?..... YES .....

working sketch here or a
which courses used, and

TEN
TENSILE S



SEAM ON 1st COURSE

SEAM ON 2nd COURSE

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

Boiler Form No. 4

B. L. W. Form 491
6M 2-21

12 28 1/4 E 21

THE BALDWIN LOCOMOTIVE WORKS

-B-

Specification Card for Locomotive No. 18

Owned by ..... TEMPLE LUMBER ..... Railroad Company.

Operated by ..... TEMPLE LUMBER ..... Railroad Company.

Builder, The Baldwin Locomotive Works.
Builder's No. of Boiler 55382
When built ..... MAY, 1922.
Where built ..... EDDYSTONE, PENNA.
Type of boiler EXT. WAGON TOP-RADIAL STAYS
Material of boiler shell sheets .. STEEL
Material of rivets ..... STEEL
Dome, where located .... ON 3RD COURSE
Grate area in sq. ft. 22.2
Height of lowest reading of gauge glass above crown sheet ..... 3 1/4"
Height of lowest gauge cock above crown sheet .... 3 1/4"
Water-bar tubes, O. diam. .... --- .... thickness. ---
Arch tubes, O. diam. ..... --- .... thickness. ---
Fire tubes, number 190
" " O. diam. ..... 2" ..... length ... 168"

Safety valves:

No.	Size	Make	Style
2	2 1/2"	CROSBY	OPEN

Firebox stay bolts, O. diam. .. 7/8" .. spaced 3.86" x .. 4"
Combustion chamber stay bolts, O. diam. .... ---
" " " " spaced .... --- x ---
Crown stays, O. diam., top .... 1" ..... bottom ... 1"
" " spaced .. 3.99" ..... x 3.835"
Crown-bar rivets, O. diam., top .... --- . bottom --- ....
" " " spaced ..... --- x ---
Water space at firebox ring, sides ..... 3"
back ..... 3" ..... front ..... 4"
Width of water space at sides of firebox measured at center line of boiler, front 5" back 8"

Shell sheets:

Front tube	1/2"	thick.	
1st course	9/16"	" 54 7/8"	I. diam.
2d "	5/8"	" 56" TO 60"	"
3d "	5/8"	" 61 1/4"	"
4th "	---	" ---	"

Mem.: When courses are not cylindrical give inside diameter at each end.

Firebox:
Thickness of sheets—
Tube ..... 1/2" .... Crown ... AND .. Sides .. 3/8" ....
Door .. 5/16" .... Combustion chamber. --- .....
Inside throat (if tube sheet is in two pieces) .---..

External firebox:
Thickness of sheets—throat 11/16" .. back head .. 1/2" ...
Roof ..... AND ..... sides .. 9/16" .....
Dome inside diam. .... 29" .....
Thickness of sheet .. 3/4" .... base .. 1" .... liner .. 5/8" ....

Were you furnished with authentic records of the tests of materials used in boiler? ..... YES .....

Records on file in the office of the Test Department of The Baldwin Locomotive Works show that the lowest tensile strength of the sheets in shell of this boiler is:

1st course	57600	pounds per sq. in.
2d "	57500	" " " "
3d "	59000	" " " "
4th "	---	" " " "


Is boiler shell circular at all points? ... YES .....
If shell is flattened, state location and amount .....
..... ---- .....
Are all parts thoroughly stayed? ..... YES .....
Are dome and other openings sufficiently reinforced?
..... YES .....
Is boiler equipped with fusible plugs? ..... YES .....

ng of longitudinal and circumferential seams used in shell of boiler,
ated efficiency of weakest longitudinal seam.

ENGTH DOME 60900 LBS. PER SQ. IN.
DOME LINER 59000 LBS. PER SQ. IN.

SEAM ON 2nd COURSE.

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076




SEAM ON 3rd COURSE.

EFFICIENCY: 82.2%

HOLES FOR RIVETS $\frac{1}{16}$" LARGER THAN RIVET SIZES GIVEN.

Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076



Scanned from an original at The History Center, Diboll, TX www.thehistorycenteronline.com 2000:076

* WHITWORTH THREADS, 12 PER INCH.

The maximum stresses at the allowed working pressure were found by calculation to be as follows:

* Stay bolts at root of thread....6660.....lbs. per sq. in.
* Stay bolts at reduced section...6990..... " " " "
* Crown stays [redacted] at [redacted] smallest section, [redacted]...5090.....lbs. per sq. in.
Crown [redacted] crown-bar rivets [redacted] at root of thread on smallest section [redacted]...---.....lbs. per sq. in.

Round [redacted] braces..8600.....lbs. per sq. in.
Gusset braces .....---..... " " " "
Shearing stress on rivets.....8130..... " " " "
Tension on net section of plate in longitudinal seam of lowest efficiency, pounds per sq. in....11920.....

Dimensions and data taken from locomotive were furnished by .....---.....

Data upon which above calculations were made was obtained from Drawing No..14392.....

dated.....---..... furnished by The Baldwin Locomotive Works.

John C. Da Costa
Mechanical Engineer.

STATE OF PENNSYLVANIA, }
COUNTY OF PHILADELPHIA, } SS.:

.....JOHN. C. DACOSTA.....being duly sworn says that he is the officer who signed the foregoing specification, that he has satisfied himself of the correctness of the drawings and data used, and verified all of the calculations, and has examined the record of present condition of boiler dated.....
.....MAY. 8,. 1922.....and sworn to by inspectors. H. P. SPAIN & W. H. WRIGHT.....
and believes that the design, construction, and condition of boiler No....55382.....renders it safe for a working pressure of.....200.....pounds per square inch.

John C. Da Costa
(Name of affiant.)

Subscribed and sworn to before me
this..11th...day of.....May.....1922.

Irvin M. Pfeffer
Notary Public.

NOTARY PUBLIC,
My Commission Expires Jan. 23, 1925.

Approved:

.....